


SYLLABUS PLAN OF 5TH SEMESTER(2026-27) CIVIL ENGINEERING


Discipline:- CIVIL ENGG.	Semester:- 5 TH	Name of the Teaching Faculty SWAGATIKA SAMAL (LECTURER)
Subject:- ADVANCED CONSTRUCTION TECHNOLOGY(TH.4)	No of Days/ per Week Class Allotted :- 03	Semester From:- 01/07/2026 To:- 05/11/2026
		No of Weeks:- 19
Week	Class Day	Theory/ Practical Topics
1 st	1 st	UNIT –I Advanced Construction Materials • Fibres: Use and properties of steel, polypropylene, carbon and glass fibres.
	2 nd	• Plastics: Use and properties of PVC, RPVC
	3 rd	HDPE, FRP, GRP
2 nd	1 st	• Miscellaneous Materials: Properties and uses of acoustics materials
	2 nd	wall claddings, plaster boards, micro-silica
	3 rd	waterproofing materials, adhesives.
3 rd	1 st	• Use of waste products and industrial by products in bricks, blocks, concrete and mortar.
	2 nd	UNIT –II Advanced Concreting Methods and Equipments • Ready Mix Concrete: Necessity and use of ready mix concrete
	3 rd	Products and equipments for ready mix concrete plant
4 th	1 st	Conveying of ready mix concrete
	2 nd	transit mixers ,Function
	3 rd	• Vibrators for concrete consolidation
5 th	1 st	Internal, needle, surface, platform and form vibrators.
	2 nd	• Underwater Concreting
	3 rd	Procedure and equipments required for Tremie method,
6 th	1 st	Drop bucket method. Properties
	2 nd	workability and water cement ratio of the concrete
	3 rd	• Special concrete: procedure and uses of special concretes
7 th	1 st	Roller compacted concrete,
	2 nd	Self-compacting concrete (SCC), Steel fibre reinforced concrete
	3 rd	Foam concrete, shotcreting.
8 th	1 st	UNIT –III Advanced Technology in Constructions • Construction of bridges and flyovers
	2 nd	Equipments and machineries required for foundation and super structure.
	3 rd	• Construction of multi-storeyed Building
9 th	1 st	Equipments and machinery required for construction of multi-storeyed building such as use of lifts, belt conveyers,
	2 nd	pumping of concrete.
	3 rd	• Prefabricated construction: Methods of prefabrication
10 th	1 st	Plant fabrication and site fabrication,
	2 nd	All prefabricated building elements such as wall panels, slab panels, beams, columns,
	3 rd	door and window frames etc. Equipments and machineries used for placing
11 th	1 st	Jointing of prefabricated elements.
	2 nd	• Strengthening of embankments by soil reinforcing techniques using geo-synthetics
	3 rd	



12 th	1 st	UNIT -IV Hoisting and Conveying Equipments • Hoisting Equipments: Principles and working of Derrick-Pole
	2 nd	Gin Pole, Crane, Power driven scotch derrick crane
	3 rd	Hand operated crane, Locomotive crane, Tower crane, Lattice Girder,
13 th	1 st	Winches, Elevators, ladders. Crawler cranes
	2 nd	Truck mounted cranes, Gantry cranes, Mast cranes
	3 rd	• Conveying Equipments ,Introduction
14 th	1 st	Working of belt conveyers
	2 nd	types of belts and conveying mechanism.
	3 rd	Capacity and use of dumpers, tractors and trucks
15 th	1 st	UNIT -V Miscellaneous Machineries and Equipments • Excavation Equipments
	2 nd	Use, working and output of following machinery – bull dozers
	3 rd	scrapers, graders, Clam Shell, trenching equipment,
16 th	1 st	Tunnel boring machine, Wheel mounted belt loaders
	2 nd	power shovels, JCB, and drag lines.
	3 rd	• Compacting Equipments: Output of different types of rollers such as plain rollers
17 th	1 st	ship footed rollers, vibratory, pneumatic rollers rammers
	2 nd	• Miscellaneous Equipments: Working and selection of equipments
	3 rd	Pile driving equipments,
18 th	1 st	Pile hammers, Hot mix bitumen plant
	2 nd	bitumen paver, grouting equipment
	3 rd	guniting equipments, floor polishing and cutting machine
19 th	1 st	selection of drilling pattern for blasting
	2 nd	Bentonite/mud slurry in drilling,
	3 rd	Explosives for blasting, Dynamite, process of using explosives

S. Samal
23.06.26
LECTURER


PRINCIPAL 23/6/26
Principal
GIET (Polytechnic)
Jagatpur, Cuttack


23.06.2026
SR.LECTURER
Sr. Lecturer
Civil Engg. Dept.
G.I.E.T(Poly), Jagatpur, Cta.